

GPS #: 5111R1

Date Destroyed:

Date Revised: 7/4/2011

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/H-6

City / Location: Huntington Beach

Scale Factor: 0.99997761

Ellipsoid Red. Factor: 1.00000475

Combination Factor: 0.99998236

Convergence Angle: -00 57 42.39710

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 37.56854	118 00 00.79408	2212661.270	6029522.921	
2007.00	33 43 37.58490	118 00 00.81114	2212662.95	6029521.51	

References: RSB 150/1-9, CR 2001-0698, CR 2011-0201, CR 2011-0528

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "5111R1 3-01" FLUSH, IN LIEU OF PUNCHED SPIKE AND WASHER, (ILLEGIBLE). MONUMENT WAS RESET PER CORNER RECORD # 2001-698. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF GOTHARD ST. AND MURDY CIRCLE.

