

**GPS #:** 5111R2

Date Destroyed:

Date Revised: 7/4/2014

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/H-6

City / Location: Huntington Beach

Scale Factor: 0.99997761

Ellipsoid Red. Factor: 1.00000475

Combination Factor: 0.99998236

Convergence Angle: -00 57 42.39710

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 37.56854	118 00 00.79408	2212661.270	6029522.921	
2007.00	33 43 37.58490	118 00 00.81114	2212662.95	6029521.51	

References: RSB 150/1-9, CR 2001-0698, CR 2011-0201, CR 2011-0528, CR 2011-2466

**Description:**

FD SPIKE AND WASHER STAMPED "RCE 27743", FLUSH PER CR 2011-2466 IN LIEU OF PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "5111R1 3-01" FLUSH, ORIGINAL MONUMENT BEING PUNCHED SPIKE AND WASHER, (ILLEGIBLE). MONUMENT WAS RESET PER CORNER RECORD # 2001-698. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF GOTHARD ST. AND MURDY CIRCLE.

