

GPS #: **5117R2**

Date Destroyed:

Date Revised: 9/11/2011

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/B-6

City / Location: Huntington Beach

Scale Factor: 0.99997793

Ellipsoid Red. Factor: 1.00000512

Combination Factor: 0.99998305

Convergence Angle: -00 59 30.30256

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 46.98267	118 03 17.15808	2213895.447	6012956.786	
2007.00	33 43 46.99897	118 03 17.17518	2213897.12	6012955.37	

References: MM 530/42-48, RSB 150/1-9, CR 2001-0699, CR 2011-2734

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS OCS WASHER STAMPED "GPS 5117R2" PER CR 2011-2734 FLUSH, IN LIEU OF PUNCHED SPIKE AND WASHER STAMPED "5117R1 3-01". STATION IS LOCATED AT CENTERLINE INTER OF SAYBROOK LN. AND EDINGER AVE.

