

GPS #: **5131R2**

Date Destroyed:

Date Revised: 2/2/2010

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/D-4

City / Location: Huntington Beach

Scale Factor: 0.99997972

Ellipsoid Red. Factor: 1.00000478

Combination Factor: 0.99998450

Convergence Angle: -00 59 04.61656

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

No PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 39.59797	118 02 30.41527	2219145.030	6016995.397	
2007.00	33 44 39.61426	118 02 30.43227	2219146.70	6016993.99	

References: RSB 150/1-9, CR 2002-0532, CR 2007-2915

Description:

FD GEAR SPIKE AND WASHER STAMPED (LS 6970) PER CR 2007-2915 PREVIOUS MONUMENT BEING; PUNCHED SPIKE AND OCS BRASS TAG STAMPED "4-02 5131R1" FLUSH, IN LIEU OF PK NAIL AND WASHER. MONUMENT WAS RESET PER CORNER RECORD # 2002-532. STATION IS LOCATED IN THE INTERSECTION OF BOLSA CHICA ST. AND BOLSA AVE.

