

GPS #: 5134

Date Destroyed:

Date Revised: 3/18/2012

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/D-3

City / Location: Huntington Beach

Scale Factor: 0.99998046

Ellipsoid Red. Factor: 1.00000472

Combination Factor: 0.99998518

Convergence Angle: -00 59 04.79726

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 00.82398	118 02 30.74411	2221290.761	6017004.505	-98.605
2007.00	33 45 00.84026	118 02 30.76107	2221292.43	6017003.10	

References: RSB 150/1-9, CR 2007-2914, CR 2012-0298, CR 2012-0763

Description:

FD 1 1/2" ALUMINUM WASHER IN CONC., DOWN 1.50' IN WELL MONUMENT PER CR 2007-2914. STATION IS LOCATED AT INTER OF BOLSA CHICA RD. AND RANCHO RD.

