

GPS #: 5138R1

Date Destroyed:

Date Revised: 4/11/2001

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/E-1

City / Location: Westminster

Scale Factor: 0.99998163

Ellipsoid Red. Factor: 1.00000445

Combination Factor: 0.99998608

Convergence Angle: -00 58 49.03340

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 33.80612	118 02 02.05739	2224582.650	6019483.440	
2007.00	33 45 33.82239	118 02 02.07442	2224584.32	6019482.03	

References: MM 370/46-48, RSB 150/1-9, CR 2001-0771

Description:

FD GEAR SPIKE AND WASHER STAMPED "RCE 18752" FLUSH, IN LIEU OF HEX ROD DOWN 1.6' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2001-771. STATION IS LOCATED ALONG THE CENTERLINE OF WESTMINSTER BLVD., 171.27' W'LY FROM ITS CENTERLINE INTER WITH MILAN ST.

