

GPS #: **5139R1**

Date Destroyed:

Date Revised: 4/11/2001

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/D-1

City / Location: Westminster

Scale Factor: 0.99998164

Ellipsoid Red. Factor: 1.00000462

Combination Factor: 0.99998626

Convergence Angle: -00 59 06.28441

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 33.92595	118 02 33.45036	2224640.216	6016833.550	
2007.00	33 45 33.94215	118 02 33.46742	2224641.88	6016832.14	

References: PMB 50/20, RSB 150/1-9, CR 2001-0772

Description:

FD GEAR SPIKE AND WASHER STAMPED "RCE 18752" FLUSH, IN LIEU OF 3/4" HEX SPIKE, DOWN 1.55' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2001-772. STATION IS LOCATED AT CENTERLINE INTER OF BOLSA CHICA ST. AND WESTMINSTER BLVD.

