

GPS #: **5141**

Date Destroyed:

Date Revised: 7/22/2016

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/A-2

City / Location: Seal Beach

Scale Factor: 0.99998164

Ellipsoid Red. Factor: 1.00000490

Combination Factor: 0.99998654

Convergence Angle: -00 59 40.87967

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 34.13992	118 03 36.40606	2224753.671	6011519.417	-102.359
2007.00	33 45 34.15620	118 03 36.42320	2224755.34	6011518.00	

References: A/5-11&12 236, RSB 150/1-9, CR 2009-1973, CR 2009-3104, CR 2015-1179, CR 2016-1179

Description:

FD PUNCHED HEX ROD IN WELL MONUMENT.
STATION IS LOCATED AT CENTERLINE OF
WESTMINSTER BLVD., 1.0 MILE W'LY OF BOLSA
CHICA RD.

