

GPS #: **5148R2**

Date Destroyed:

Date Revised: 6/2/2004

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 797/C-7

City / Location: Westminster

Scale Factor: 0.99998259

Ellipsoid Red. Factor: 1.00000442

Combination Factor: 0.99998701

Convergence Angle: -00 59 06.21054

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 00.11982	118 02 33.31597	2227287.376	6016890.417	
2007.00	33 46 00.13604	118 02 33.33307	2227289.04	6016889.00	

References: MM 123/1-4, RSB 150/1-9, CR 2001-0773, CR 2004-0072, CR 2004-0357

Description:

FOUND PK NAIL AND WASHER STAMPED "LS 6970" IN LIEU OF PUNCHED SPIKE AND 1 1/2" BRASS OCS WASHER STAMPED "5148R1 3-01" FLUSH, IN LIEU OF SPIKE. MONUMENT WAS RESET PER CORNER RECORD # 2004-0357. STATION IS LOCATED ALONG THE CENTERLINE OF BOLSA CHICA RD., 140'+/- S'LY FROM ITS INTER WITH DUNCANNON AVE.

