

GPS #: 5175R3

Date Destroyed:

Date Revised: 7/28/2009

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 709/G-7

City / Location: Brea

Scale Factor: 1.00000605

Ellipsoid Red. Factor: 0.99998389

Combination Factor: 0.99998993

Convergence Angle: -00 52 48.00022

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 06.14359	117 51 05.05715	2281530.073	6075834.731	
2007.00	33 55 06.16038	117 51 05.07395	2281531.79	6075833.34	

References: RSB 149/1-9, CR 2001-0102, CR 2005-0154, CR 2007-1170, CR 2008-2136

Description:

FD 1" IP WITH TAG STAMPED "LS 5411" IN MEDIAN IN LIEU OF GEAR SPIKE AND WASHER STAMPED "LS 6970" IN LIEU OF PUNCHED SPIKE AND OCS WASHER FLUSH, ORIGINAL MONUMENT BEING PK NAIL. MONUMENT WAS RESET PER CORNER RECORD # 2005-0154. MONUMENT IS LOCATED ALONG THE VISUAL CENTERLINE OF BIRCH ST., 0.2 MILE W'LY FROM VALENCIA AVE.

