

**GPS #:** 5193R1

Date Destroyed:

Date Revised: 1/18/2001

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 739/H-3

City / Location: Placentia

Scale Factor: 1.00000270

Ellipsoid Red. Factor: 0.99998800

Combination Factor: 0.99999070

Convergence Angle: -00 52 37.23112

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 57.26155	117 50 45.45974	2274542.469	6077379.531	
2007.00	33 53 57.27826	117 50 45.47669	2274544.18	6077378.13	

References: RSB 149/1-9, CR 2001-0098

## Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND BRASS 1 1/4" OCS WASHER STAMPED "5193R1 12/00" FLUSH, IN LIEU OF CONC. NAIL. MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-098. MONUMENT IS LOCATED IN THE INTER OF BASTANCHURY RD. AND SPAHN LN.

