

GPS #: 5194R1

Date Destroyed:

Date Revised: 3/12/2013

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 739/F-3

City / Location: Placentia

Scale Factor: 1.00000233

Ellipsoid Red. Factor: 0.99998937

Combination Factor: 0.99999169

Convergence Angle: -00 52 59.40860

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 49.41624	117 51 25.81787	2273801.758	6073965.775	
2007.00	33 53 49.43295	117 51 25.83484	2273803.47	6073964.37	

References: MM 276/28-30, RSB 149/1-9, CR 2012-3558, CR 2012-4306

Description:

FD GEAR SPIKE WITH WASHER STAMPED "LS 5411"
FLUSH PER CR 2012-4306, IN LIEU OF PUNCHED
SPIKE AND WASHER AT THE CENTERLINE INTER OF
MICHEL PLACE AND MICHEL WAY.

