

GPS #: **5196R1**

Date Destroyed:

Date Revised: 1/18/2001

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 740/F-7

City / Location: Yorba Linda

Scale Factor: 0.99999680

Ellipsoid Red. Factor: 0.99998971

Combination Factor: 0.99998651

Convergence Angle: -00 50 29.07075

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 49.66820	117 46 52.23635	2261351.120	6096847.180	
2007.00	33 51 49.68453	117 46 52.25288	2261352.79	6096845.81	

References: RSB 149/1-9, CR 2001-0097

Description:

FD PUNCHED SPIKE AND OCS BRASS 1 1/4" WASHER STAMPED "5196R1 12/00" FLUSH, IN LIEU OF PK NAIL. MONUMENT WAS RESET PER CORNER RECORD # 2001-097. MONUMENT IS LOCATED ALONG THE CENTER OF ESPERANZA RD., 0.14 MILE WEST OF FAIRMONT BLVD. CONNECTOR.

