

GPS #: 5204R1

Date Destroyed:

Date Revised: 9/13/2007

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 740/H-4

City / Location: Yorba Linda

Scale Factor: 1.00000125

Ellipsoid Red. Factor: 0.99997838

Combination Factor: 0.99997963

Convergence Angle: -00 49 53.73303

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 26.69540	117 45 47.92953	2271079.024	6102411.821	
2007.00	33 53 26.71187	117 45 47.94597	2271080.71	6102410.46	

References: RSB 149/1-9, CR 2007-0382, CR 2007-0949

Description:

FD SPIKE AND WASHER, STAMPED "L.S. 5411", FLUSH. IN LIEU OF FD SPIKE AND WASHER STAMPED "LS 4453". PER CORNER RECORD 2007-0949. AT THE INTERSECTION OF DORINDA RD. AND YORBA LINDA BLVD.

