

GPS #: **5215R1**

Date Destroyed:

Date Revised: 9/24/2009

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 739/B-6

City / Location: Fullerton

Scale Factor: 0.99999848

Ellipsoid Red. Factor: 0.99999584

Combination Factor: 0.99999432

Convergence Angle: -00 54 20.81327

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 26.95191	117 53 53.95627	2265661.715	6061348.071	
2007.00	33 52 26.96846	117 53 53.97333	2265663.41	6061346.66	

References: A/3-10 392, RSB 149/1-9, CR 2007-0253, CR 2009-0576, CR 2009-1756

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5411", FLUSH, IN LIEU OF SQUARE SPIKE, NO PUNCH, DOWN 0.3' IN A.C., LOCATED AT THE CENTERLINE INTERSECTION OF CHAPMAN AVE. AND ACACIA AVE.

