

GPS #: **5227R1**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 770/E-1

City / Location: Anaheim

Scale Factor: 0.99999661

Ellipsoid Red. Factor: 0.99999136

Combination Factor: 0.99998797

Convergence Angle: -00 50 51.32932

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 45.51767	117 47 32.74200	2260981.948	6093425.582	
2007.00	33 51 45.53389	117 47 32.75855	2260983.61	6093424.21	

References: RSB 149/1-9, CR 2009-2373, CR 2009-3260

Description:

FD BRASS PIN AND 1" ALUMN. TAG STAMPED "CALIFORNIA DEPARTMENT OF TRANSPORTATION" FLUSH IN EPOXY IN LIEU OF GEAR SPIKE AND WASHER, STAMPING UNREADABLE, LOCATED ALONG THE APPARENT CENTERLINE OF ORANGETHORPE AVE., 70'+/- EAST FROM ITS INTER WITH VIA BREVE.

