

GPS #: 5231

Date Destroyed:

Date Revised: 8/8/2006

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 769/J-1

City / Location: Anaheim

Scale Factor: 0.99999663

Ellipsoid Red. Factor: 0.99999394

Combination Factor: 0.99999057

Convergence Angle: -00 52 19.58251

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 45.94894	117 50 13.34323	2261228.778	6079884.402	126.581
2007.00	33 51 45.96535	117 50 13.36002	2261230.46	6079883.01	

References: PMB 82/41-42, RSB 149/1-9, CR 2005-1604

Description:

FD 2" PUNCHED BRASS DISK DOWN 2.0' IN WELL MONUMENT, LOCATED AT THE CENTERLINE INTER OF JEFFERSON ST. AND MIRALOMA AVE.

