

GPS #: 5237

Date Destroyed: 8/3/2006

Date Revised: 8/3/2006

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 769/B-1

City / Location: Fullerton

Scale Factor: 0.99999613

Ellipsoid Red. Factor: 0.99999667

Combination Factor: 0.99999279

Convergence Angle: -00 54 20.34910

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 34.64772	117 53 53.11159	2260374.036	6061335.715	69.646
2007.00	33 51 34.66424	117 53 53.12904	2260375.73	6061334.27	

References: RSB 149/1-9

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" X 2" HUB WITH TACK DOWN 0.1' AT THE APPARENT CENTERLINE INTER OF ORANGETHORPE AVE. AND ACACIA AVE.

NO
LOCATION
MAP