

GPS #: **5241R1**

Date Destroyed:

Date Revised: 2/25/2013

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 769/H-2

City / Location: Anaheim

Scale Factor: 0.99999519

Ellipsoid Red. Factor: 0.99999440

Combination Factor: 0.99998959

Convergence Angle: -00 52 39.08331

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 13.51391	117 50 48.83034	2257996.140	6076841.941	
2007.00	33 51 13.53029	117 50 48.84725	2257997.82	6076840.54	

References: PMB 90/5-6, RSB 149/1-9, CR 2011-3814, CR 2012-1608

Description:

FD 2"ALUM. CAP STAMPED "ANAHEIM SURVEY PLS6871" DOWN 0.8' IN WELL PER CR 2012-1608, IN LIEU OF, SPIKE AND BRASS CITY OF ANAHEIM WASHER FLUSH IN A.C., LOCATED AT THE CENTERLINE INTER OF LA PALMA AVE. AND MILLER ST.

