

GPS #: 5242

Date Destroyed:

Date Revised: 4/24/2013

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 769/J-2

City / Location: Anaheim

Scale Factor: 0.99999547

Ellipsoid Red. Factor: 0.99999399

Combination Factor: 0.99998946

Convergence Angle: -00 52 20.07316

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 19.85148	117 50 14.23610	2258592.156	6079768.956	125.643
2007.00	33 51 19.86784	117 50 14.25294	2258593.83	6079767.56	

References: RSB 149/1-9, PMB 253/41-43, CR 2011-3819, CR 2012-1612

Description:

FD 2" PUNCHED BRASS CAP TAGGED LS 5831 DOWN 0.3' IN WELL MONUMENT, LOCATED AT THE CENTERLINE INTER OF LA PALMA AVE. AND TUSTIN AVE.

