

GPS #: 5247R1

Date Destroyed:

Date Revised: 1/23/2004

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 769/E-4

City / Location: Anaheim

Scale Factor: 0.99999260

Ellipsoid Red. Factor: 0.99999577

Combination Factor: 0.99998837

Convergence Angle: -00 53 28.09687

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 13.56132	117 52 18.02412	2252052.658	6069226.175	
2007.00	33 50 13.57743	117 52 18.04145	2252054.31	6069224.74	

References: A/4-9 794, RSB 149/1-9, CR 2000-0527, CR 2001-1011

Description:

FD SPIKE AND CITY OF ANAHEIM TAG. MONUMENT WAS RESET PER CORNER RECORD #2001-1011B IN LIEU OF, RAIL ROAD SPIKE, DOWN 0.2', IN LIEU OF SQUARE HEAD SPIKE DOWN 0.27' IN A.C., LOCATED AT THE CENTERLINE INTER OF LINCOLN AVE. AND RIO VISTA.

