

GPS #: **5257R1**

Date Destroyed:

Date Revised: 1/17/2001

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 741/F-6

City / Location: Yorba Linda

Scale Factor: 0.99999863

Ellipsoid Red. Factor: 0.99998640

Combination Factor: 0.99998503

Convergence Angle: -00 47 59.68158

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 30.19590	117 42 20.38120	2265119.151	6119827.038	
2007.00	33 52 30.21253	117 42 20.39747	2265120.85	6119825.69	

References: RSB 149/1-9, CR 2001-0091

Description:

FD PUNCHED SPIKE AND 1 1/2" WASHER STAMPED "LS 4453" IN LIEU OF GEAR SPIKE. MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-091. MONUMENT IS LOCATED AT THE RADIUS POINT OF THE SAN REMO WAY CUL-DE-SAC.

