

GPS #: 6000

Date Destroyed:

Date Revised: 5/20/2009

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 799/D-7

City / Location: Santa Ana

Scale Factor: 0.99998260

Ellipsoid Red. Factor: 0.99999995

Combination Factor: 0.99998255

Convergence Angle: -00 53 54.17169

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 00.63225	117 53 05.47452	2226551.282	6064823.169	1.027
2007.00	33 46 00.64854	117 53 05.49104	2226552.95	6064821.80	

References: A/5-10 889, RSB 150/10-23, CR 2008-1290

Description:

FD BOAT SPIKE AND O.C.S. TAG, FLUSH. STATION IS LOCATED AT THE CENTERLINE INTER OF BRISTOL ST. AND SANTA CLARA AVE.

