

GPS #: 6005

Date Destroyed:

Date Revised: 5/22/2009

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 799/J-7

City / Location: Santa Ana

Scale Factor: 0.99998264

Ellipsoid Red. Factor: 0.99999635

Combination Factor: 0.99997899

Convergence Angle: -00 52 17.04335

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 01.71043	117 50 08.72251	2226429.809	6079744.815	76.253
2007.00	33 46 01.72677	117 50 08.73862	2226431.48	6079743.48	

References: RSB 150/10-23, CR 2008-1537

Description:

FD PUNCHED 3" BRASS CAP, DOWN 0.8' IN WELL MONUMENT. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF TUSTIN AVE. AND SANTA CLARA AVE.

