

GPS #: 6009

Date Destroyed:

Date Revised: 4/1/2011

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 800/E-7

City / Location: Unin., Orange County

Scale Factor: 0.99998260

Ellipsoid Red. Factor: 0.99999238

Combination Factor: 0.99997498

Convergence Angle: -00 50 56.78106

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 00.49216	117 47 42.66295	2226121.548	6092072.206	159.193
2007.00	33 46 00.50821	117 47 42.67894	2226123.19	6092070.88	

References: A/5-9 1002, RSB 150/10-23, CR 2010-1614

Description:

FD PUNCHED 1 3/4" BRASS CAP IN CONC., DOWN 1.7' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF FOOTHILL BLVD. AND NEWPORT AVE.

