

GPS #: **6013**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 830/A-1

City / Location: Santa Ana

Scale Factor: 0.99998169

Ellipsoid Red. Factor: 0.99999713

Combination Factor: 0.99997883

Convergence Angle: -00 52 14.06297

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 35.53613	117 50 03.29887	2223777.386	6080162.436	59.934
2007.00	33 45 35.55248	117 50 03.31511	2223779.06	6080161.09	

References: PMB 92/34, RSB 150/10-23, CR 2003-1025

Description:

FD PUNCHED HEX BAR IN CONC., DOWN 1.1' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF 17th ST. AND TUSTIN AVE.

