

GPS #: 6022

Date Destroyed:

Date Revised: 4/23/2015

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/D-2

City / Location: Santa Ana

Scale Factor: 0.99998063

Ellipsoid Red. Factor: 1.00000059

Combination Factor: 0.99998121

Convergence Angle: -00 53 54.62289

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 05.57222	117 53 06.29561	2220987.448	6064666.584	-12.218
2007.00	33 45 05.58854	117 53 06.31207	2220989.12	6064665.22	

References: PMB 150/12-13, RSB 150/10-23, CR 2004-1781, CR 2015-0230

Description:

FD 3 3/4" BRASS DISK WITH CHISELED "+", DOWN 1.2' IN CSA WELL MONUMENT. STATION IS LOCATED ALONG THE CENTERLINE OF BRISTOL ST., 5.00' N'LY FROM ITS CENTERLINE INTER WITH CIVIC CENTER DR, PER CR 2015-0230.

