

**GPS #:** **6023R1**

Date Destroyed:

Date Revised: 4/29/2002

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/E-2

City / Location: Santa Ana

Scale Factor: 0.99998063

Ellipsoid Red. Factor: 1.00000009

Combination Factor: 0.99998072

Convergence Angle: -00 53 37.57738

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 05.60508	117 52 35.27654	2220949.807	6067285.467	
2007.00	33 45 05.62152	117 52 35.29306	2220951.49	6067284.10	

References: PMB 188/2-3, RSB 150/10-23, CR 2001-1691

**Description:**

FD PUNCHED 3" BRASS DISK DN 1' IN WELL MONUMENT IN LIEU OF PUNCHED 2 1/2" BRASS DISK IN CONC., DOWN 0.6' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2001-1691B. MONUMENT IS LOCATED 10' E'LY OF ANOTHER WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF CIVIC CENTER DR. AND FLOWER ST. (E'LY).

