

GPS #: 6037

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/G-3

City / Location: Santa Ana

Scale Factor: 0.99997949

Ellipsoid Red. Factor: 0.99999993

Combination Factor: 0.99997942

Convergence Angle: -00 52 58.97718

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 33.04193	117 51 25.03275	2217566.684	6073165.193	1.516
2007.00	33 44 33.05832	117 51 25.04932	2217568.36	6073163.82	

References: MM 679/47-48, RSB 150/10-23, CR 2008-3130

Description:

FD PUNCHED 2 1/2" BRASS DISK IN CONC.,
STAMPED "C.S.A. SURVEY 1989", DOWN 1.0' IN WELL
MONUMENT. STATION IS LOCATED AT CENTERLINE
INTER OF CHESTNUT AVE. AND STANDARD AVE.

