

GPS #: 6040

Date Destroyed: 5/3/2016

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/D-3

City / Location: Santa Ana

Scale Factor: 0.99997985

Ellipsoid Red. Factor: 1.00000116

Combination Factor: 0.99998102

Convergence Angle: -00 53 54.80721

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 43.47310	117 53 06.63102	2218754.342	6064603.235	-24.327
2007.00	33 44 43.48950	117 53 06.64761	2218756.02	6064601.86	

References: SANTA ANA TIE BOOK 11 PAGE 262, RSB 150/10-23

Description:

DESTROYED - FD 3 1/2" BRASS CAP WITH CHISELED "+", DOWN 0.8' IN WELL MONUMENT. STATION IS LOCATED ALONG THE SURVEY CENTERLINE OF FIRST ST. AND WEST FROM THE CENTERLINE OF BRISTOL ST.

