

GPS #: 6042R1

Date Destroyed: 1/6/2012

Date Revised: 6/2/2011

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/B-3

City / Location: Santa Ana

Scale Factor: 0.99998027

Ellipsoid Red. Factor: 1.00000155

Combination Factor: 0.99998181

Convergence Angle: -00 54 29.21104

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 55.29868	117 54 09.23836	2220032.893	6059336.096	R1
2007.00	33 44 55.31495	117 54 09.25508	2220034.56	6059334.71	

References: PMB 198/19-20, RSB 150/10-23, CR 2004-0679, CR 2011-1766

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD LEAD AND TACK WITH CITY OF SANTA ANA TAG, FLUSH IN CONC. PER CR 2011-1766, IN LIEU OF 3 1/2" BRASS DISK WITH CHISELED "+", DOWN 1.8' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF FIFTH ST. AND SULLIVAN ST.