

GPS #: 6043R1

Date Destroyed:

Date Revised: 9/11/2011

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/B-4

City / Location: Santa Ana

Scale Factor: 0.99997894

Ellipsoid Red. Factor: 1.00000211

Combination Factor: 0.99998105

Convergence Angle: -00 54 29.15848

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 17.03005	117 54 09.14270	2216164.980	6059282.865	R1
2007.00	33 44 17.04634	117 54 09.15953	2216166.65	6059281.47	

References: MM 608/47-48, RSB 150/10-23, CR 2011-0630, CR 2011-1322

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5411", FLUSH PER CR 2011-1322 IN LIEU OF GEAR SPIKE AND WASHER (ILLEGIBLE) FLUSH, ACCEPTED AS SPIKE AND WASHER STAMPED "RCE 12437", PER MM 608/47-48. STATION IS LOCATED AT CENTERLINE INTER OF SULLIVAN ST. AND MONTA VISTA AVE.

