

**GPS #:** 6048R1

Date Destroyed:

Date Revised: 9/13/2007

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/C-5

City / Location: Santa Ana

Scale Factor: 0.99997850

Ellipsoid Red. Factor: 1.00000233

Combination Factor: 0.99998084

Convergence Angle: -00 54 12.27855

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 44 04.07667 | 117 53 38.42500 | 2214814.786   | 6061856.006  |                       |
| 2007.00          | 33 44 04.09302 | 117 53 38.44183 | 2214816.46    | 6061854.61   |                       |

References: RSB 150/10-23, CR 2001-932, CR 2007-0428

## Description:

FD "CSA" WELL MONUMENT W/ 3" BRASS DISC WITH "+", DN. 0.9'. IN LIEU OF PUNCHED BOLT AND WASHER (NO STAMPING), FLUSH. MONUMENT RESET PER CORNER RECORD 2007-0428. LOCATED 1.0' E'LY FROM ANOTHER BOLT AND WASHER. STATION IS LOCATED AT THE INTERSECTION OF MCFADDEN AVE. AND RAITT ST.

