

GPS #: 6058

Date Destroyed:

Date Revised: 10/16/2006

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 830/A-5

City / Location: Tustin

Scale Factor: 0.99997828

Ellipsoid Red. Factor: 1.00000051

Combination Factor: 0.99997878

Convergence Angle: -00 52 00.98579

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 57.38066	117 49 39.50130	2213826.297	6082021.284	-10.604
2007.00	33 43 57.39709	117 49 39.51812	2213827.98	6082019.89	

References: A/5-9 40, RSB 150/10-23, CR 2006-0215, CR 2006-0762

Description:

FD PUNCHED 2 1/4" ALUMINUM O.C.S. CAP, SET IN CONC., DOWN 1.3' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF NEWPORT AVE. AND WALNUT AVE.

