

GPS #: **6061R1**

Date Destroyed:

Date Revised: 9/16/2009

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/J-6

City / Location: Santa Ana

Scale Factor: 0.99997757

Ellipsoid Red. Factor: 1.00000110

Combination Factor: 0.99997867

Convergence Angle: -00 52 28.10839

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 36.35057	117 50 28.85840	2211764.133	6077820.856	
2007.00	33 43 36.36703	117 50 28.87525	2211765.82	6077819.46	

References: MM 255/15-16, RSB 150/10-23, CR 2007-1262, CR 2007-1513

Description:

FD GEAR SPIKE WITH "CITY OF SANTA ANA" WASHER PER CR 2007-1513, FLUSH IN LIEU OF PUNCHED SQUARE SPIKE WITH SANTA ANA SURVEY TAG, FLUSH. STATION IS LOCATED AT CENTERLINE INTER OF EDINGER AVE. AND RITCHEY ST.

