

**GPS #:** **6074**

**Date Destroyed:** **8/11/2006**

**Date Revised:** 4/3/2001

**Benchmark Designation:**

**OCS Index Map:** 5LA

**Page/Grid:** 829/F-6

**City / Location:** Santa Ana

**Scale Factor:** 0.99997706

**Ellipsoid Red. Factor:** 1.00000245

**Combination Factor:** 0.99997951

**Convergence Angle:** -00 53 20.53816

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 20.81679	117 52 04.26898	2210318.158	6069738.986	-51.204
2007.00	33 43 20.83322	117 52 04.28580	2210319.84	6069737.59	

**References:** PMB 121/48-49, RSB 150/10-23, CR 2001-0404, CR 2006-0254

**Description:**

FD 3 1/2" BRASS CAP WITH CHISELED "+", DOWN 1.7'  
IN WELL MONUMENT LOCATED NE'LY 5'+/- FROM  
ANOTHER WELL MONUMENT. STATION IS LOCATED  
AT CENTERLINE INTER OF ST. ANDREW PLACE  
(WEST) AND MAIN ST.

NO  
LOCATION  
MAP