

GPS #: 6079

Date Destroyed: 6/6/2001

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/G-7

City / Location: Santa Ana

Scale Factor: 0.99997630

Ellipsoid Red. Factor: 1.00000265

Combination Factor: 0.99997895

Convergence Angle: -00 52 58.20753

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 57.39650	117 51 23.63215	2207898.012	6073134.491	-55.275
2007.00	33 42 57.41288	117 51 23.64905	2207899.69	6073133.09	

References: PMB 131/37-38, RSB 150/10-23

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 1/2" BRASS CAP WITH CHISELED "+", DOWN 1.1' IN WELL MONUMENT. STATION IS LOCATED ALONG THE CENTERLINE OF STANDARD AVE., 5.00' S'LY FROM ITS CENTERLINE INTER WITH WARNER AVE.

NO
LOCATION
MAP