

GPS #: 6081

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/E-7

City / Location: Santa Ana

Scale Factor: 0.99997632

Ellipsoid Red. Factor: 1.00000332

Combination Factor: 0.99997964

Convergence Angle: -00 53 37.87096

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 58.07148	117 52 35.81081	2208060.761	6067039.257	-69.298
2007.00	33 42 58.08798	117 52 35.82778	2208062.45	6067037.85	

References: PMB 62/28, RSB 150/10-23, CR 2002-1507

Description:

FD PUNCHED 2 1/2" BRASS CITY OF SANTA ANA SURVEY CAP, STAMPED "LS 5194", SET IN CONC., DOWN 1.0' IN WELL MONUMENT. STATION IS LOCATED AT THE E'LY CENTERLINE INTER OF WARNER AVE. AND FLOWER ST.

