

**GPS #:** 6082R1

Date Destroyed:

Date Revised: 10/8/2014

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 829/D-7

City / Location: Santa Ana

Scale Factor: 0.99997633

Ellipsoid Red. Factor: 1.00000330

Combination Factor: 0.99997963

Convergence Angle: -00 53 55.07738

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 42 58.33066 | 117 53 07.12269 | 2208128.326   | 6064395.040  |                       |
| 2007.00          | 33 42 58.34709 | 117 53 07.13968 | 2208130.01    | 6064393.63   |                       |

References: RSB 108/31, RSB 150/10-23, CITY OF S.A. TIE BK 1/248, CR 2011-1758, CR 2014-1448

## Description:

FD SPIKE AND CITY OF SANTA ANA WASHER IN LIEU OF ORIGINAL MONUMENT BEING A GEAR SPIKE AND WASHER, STAMPED "LS 4212", DOWN 0.2' IN A.C. STATION IS LOCATED AT CENTERLINE INTER OF WARNER AVE. AND BRISTOL ST. MONUMENT RESET PER CITY OF SANTA ANA TIE BOOK 1/248.

