

GPS #: 6085

Date Destroyed:

Date Revised: 4/3/2001

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 828/J-7

City / Location: Santa Ana

Scale Factor: 0.99997606

Ellipsoid Red. Factor: 1.00000318

Combination Factor: 0.99997924

Convergence Angle: -00 55 03.13343

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 49.94962	117 55 10.96960	2207447.068	6053921.298	-66.489
2007.00	33 42 49.96604	117 55 10.98656	2207448.75	6053919.89	

References: RSB 101/20-23, RSB 150/10-23, CR 2001-0270, CR 2003-0413

Description:

FD PUNCHED 2 1/4" O.C.S. ALUMINUM CAP, DOWN 1.7' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF WARNER AVE. AND HARBOR BLVD.

