

GPS #: 6089R1

Date Destroyed:

Date Revised: 3/14/2001

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/D-1

City / Location: Santa Ana

Scale Factor: 0.99997533

Ellipsoid Red. Factor: 1.00000371

Combination Factor: 0.99997903

Convergence Angle: -00 53 55.37866

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 26.86029	117 53 07.67092	2204948.385	6064298.839	
2007.00	33 42 26.87674	117 53 07.68792	2204950.07	6064297.43	

References: MM 462/35-36, RSB 150/10-23, CR 2001-0275, CR 2003-1135

Description:

FD SPIKE AND CITY OF SANTA ANA WASHER ON SURFACE IN LIEU OF ORIGINAL MONUMENT BEING A PUNCHED ROUND HEAD SPIKE, NO TAG, DOWN 0.2' IN A.C. MONUMENT WAS RESET PER CORNER RECORD # 2001-275. STATION IS LOCATED AT CENTERLINE INTER OF SEGERSTROM AVE. AND BRISTOL ST.

