

**GPS #:** 6091R1

Date Destroyed:

Date Revised: 3/28/2006

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/F-1

City / Location: Santa Ana

Scale Factor: 0.99997547

Ellipsoid Red. Factor: 1.00000331

Combination Factor: 0.99997877

Convergence Angle: -00 53 20.84615

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 31.33294	117 52 04.82941	2205317.607	6069614.035	
2007.00	33 42 31.34938	117 52 04.84637	2205319.29	6069612.63	

References: PMB 177/40-42, RSB 150/10-23, CR 2003-1699, CR 2003-2198, CR 2006-0783

## Description:

FD NAIL AND CITY OF SANTA ANA WASHER ON SURFACE IN LIEU OF ORIGINAL MONUMENT BEING A FD PUNCHED ROUND HEAD SPIKE AND WASHER, STAMPED "LS 3419", DOWN 0.1' IN A.C. LOCATED AT THE CENTERLINE INTER OF DYER RD. (SOUTH) AND MAIN ST., ALSO BEING 20.00' S'LY FROM A WELL MONUMENT.

