

GPS #: 6097

Date Destroyed:
Date Revised: 12/23/1998
Benchmark Designation:
OCS Index Map: 5LA
Page/Grid: 859/E-2
City / Location: Santa Ana

Scale Factor: 0.99997449
Ellipsoid Red. Factor: 1.00000386
Combination Factor: 0.99997835
Convergence Angle: -00 53 38.52690

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 59.98751	117 52 37.00447	2202191.862	6066846.829	-80.646
2007.00	33 42 00.00400	117 52 37.02135	2202193.55	6066845.43	

References: MM 192/4-7, RSB 150/10-23

Description:

FD 3" PUNCHED BRASS DISK DOWN 0.8' IN WELL MONUMENT, ACCEPTED AS REPLACEMENT OF THE ORIGINAL GPS POINT WHICH WAS A PUNCHED ROUND SPIKE AND TAG (NO STAMPING), FLUSH. STATION IS LOCATED AT CENTERLINE INTER OF MACARTHUR BLVD. AND FLOWER ST.

