

GPS #: 6101

Date Destroyed:

Date Revised: 6/12/2008

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/A-2

City / Location: Santa Ana

Scale Factor: 0.99997448

Ellipsoid Red. Factor: 1.00000390

Combination Factor: 0.99997838

Convergence Angle: -00 54 39.39309

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 59.69704	117 54 27.76743	2202309.900	6057489.509	-81.437
2007.00	33 41 59.71344	117 54 27.78442	2202311.58	6057488.10	

References: PMB 168/35-36, RSB 150/10-23, CR 2008-0496

Description:

FD PUNCHED 2 1/2" BRASS CAP IN CONC., DOWN 1.3' IN WELL MONUMENT PER CR 2008-0496. STATION IS LOCATED AT CENTERLINE INTER OF MACARTHUR BLVD. AND FAIRVIEW ST.

