

GPS #: 6110

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/D-3

City / Location: Costa Mesa

Scale Factor: 0.99997385

Ellipsoid Red. Factor: 1.00000390

Combination Factor: 0.99997775

Convergence Angle: -00 53 55.33258

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 39.15917	117 53 07.58706	2200127.197	6064230.296	-81.532
2007.00	33 41 39.17558	117 53 07.60403	2200128.88	6064228.89	

References: PMB 194/24-26, RSB 150/10-23

Description:

FD PUNCHED 2 1/2" BRASS CAP IN CONC., STAMPED "RCE 23207", DOWN 1.8' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF BRISTOL ST. AND SUNFLOWER AVE.

