

GPS #: **6112R1**

Date Destroyed:

Date Revised: 3/24/2014

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/E-3

City / Location: Costa Mesa

Scale Factor: 0.99997385

Ellipsoid Red. Factor: 1.00000394

Combination Factor: 0.99997779

Convergence Angle: -00 53 28.74236

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 39.05096	117 52 19.19879	2200052.398	6068318.073	
2007.00	33 41 39.06737	117 52 19.21570	2200054.08	6068316.67	

References: MM 515/1-8, RSB 150/10-23, CR 2013-3234

Description:

FD PK NAIL FLUSH PER CR 2013-3234 IN LIEU OF PUNCHED 1 3/4" BRASS CAP IN CONC., STAMPED "LS 2304", DOWN 1.5' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF SUNFLOWER AVE. AND ANTON BLVD.

