

GPS #: 6115

Date Destroyed:

Date Revised: 5/21/2009

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/B-4

City / Location: Costa Mesa

Scale Factor: 0.99997325

Ellipsoid Red. Factor: 1.00000414

Combination Factor: 0.99997739

Convergence Angle: -00 54 25.87990

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 19.19719	117 54 03.17643	2198183.701	6059502.051	-86.509
2007.00	33 41 19.21368	117 54 03.19332	2198185.39	6059500.65	

References: PMB 200/36-39, RSB 150/10-23, CR 2008-1146, CR 2008-2730

Description:

FD PUNCHED 2" BRASS CAP IN CONC., STAMPED "LS 3419", DOWN 1.3' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF SOUTH COAST DR. AND SAN LEANDRO LN.

