

GPS #: **6118R1**

Date Destroyed:

Date Revised: 4/28/2004

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 858/H-4

City / Location: Costa Mesa

Scale Factor: 0.99997349

Ellipsoid Red. Factor: 1.00000414

Combination Factor: 0.99997762

Convergence Angle: -00 55 16.61924

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 27.14181	117 55 35.51076	2199111.130	6051713.904	
2007.00	33 41 27.15820	117 55 35.52769	2199112.81	6051712.50	

References: MM 277/10-13, RSB 150/10-23, CR 1996-0390

Description:

FD PK AND WASHER STAMPED "LS 5411" IN LIEU OF ORIGINAL MONUMENT BEING A PUNCHED ROUND SPIKE WITH WASHER, AND SHINER IN A.C. MONUMENT WAS RESET PER CORNER RECORD # 1996-0390. STATION IS LOCATED AT CENTERLINE INTER OF IOWA ST. AND NEW HAMPSHIRE DR.

