

GPS #: 6121R1

Date Destroyed:

Date Revised: 6/12/2008

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 858/H-4

City / Location: Costa Mesa

Scale Factor: 0.99997307

Ellipsoid Red. Factor: 1.00000360

Combination Factor: 0.99997667

Convergence Angle: -00 55 15.17797

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 13.33272	117 55 32.88798	2197711.920	6051913.057	
2007.00	33 41 13.34913	117 55 32.90493	2197713.60	6051911.65	

References: RSB 150/10-23, CR 2008-0096, CR 2008-0306

Description:

FD SPIKE AND WASHER STAMPED "LS 5411", FLUSH PER CR 2008-0306 IN LIEU OF ORIGINAL MONUMENT BEING; PUNCHED ROUND SPIKE WITH WASHER, STAMPED "LS 3999", FLUSH. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF GISLER AVE. AND GIBRALTAR AVE.

