

**GPS #:** 6131

Date Destroyed:

Date Revised: 10/21/2015

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 858/H-5

City / Location: Costa Mesa

Scale Factor: 0.99997225

Ellipsoid Red. Factor: 1.00000295

Combination Factor: 0.99997520

Convergence Angle: -00 55 19.76542

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 45.33069	117 55 41.23609	2194893.176	6051162.182	
2007.00	33 40 45.34703	117 55 41.25289	2194894.85	6051160.79	

References: RSB 150/10-23

**Description:**

FD PUNCHED ROUND HEAD SPIKE WITH WASHER, STAMPED "RCE 32140", FLUSH. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF BAKER ST. AND EAST MESA VERDE DR.

